

Daniel Weadley Roofline
14 Maguire Drive
Frimley
Surrey
GU16 9RY
07845 952 175
www.danielweadleyroofline.co.uk

Mr A. Unknown
Somewhere

Date

Re: Quotation for replacement roofline boards and guttering

Mr Unknown

Thank you for your recent enquiry regarding replacement roofline boards and guttering to your property at the above address.

Please find enclosed two quotations for your consideration.

If you have any questions or would like to instruct me further with this quotation then do not hesitate to contact me.

Yours Faithfully

Daniel Weadley

Quotation - Replacement Upvc fascia/soffits and guttering/pipes to three sides of main house, upper elevation.

Works are as follows:

- Erect access equipment to desired work height.
- Remove the first course of roof tiles and set aside for re-use.
- Cut back and remove any defective eaves felt.
- Remove and lower to ground the existing fascia, soffits, pipes and guttering.
- Supply and fit Floplast 10mm Upvc white soffit boards fixed into place with 40mm white Polytop stainless steel nails.
- Supply and fit Floplast 18mm Upvc white fascia boards fixed into place with 65mm white Polytop stainless steel nails.
- Supply and install Floplast Upvc 112mm guttering ensuring all water runs freely to the outlets.
- Supply and install Floplast Upvc rain water pipes, connect into existing underground drains..
- Supply and install 10mm over fascia vent strips – to reduce loft condensation.
- Supply and install new eaves felt overlapping into the guttering.
- Seal all Upvc boards to the wall with a silicone sealant to prevent insect infestation.
- Re-lay roof tiles.
- Lower access equipment and remove all waste material leaving the site clean and tidy.

Total Cost - £1450.00

The completed installation of Upvc fascia, soffits, pipes and guttering shall be backed by a ten year guarantee covering both workmanship and materials. The installation shall also be registered with the product manufacturer – Floplast Ltd.